

## WARRANTY ADDENDUM

This addendum to the aboveground pool warranty is to cover corrosion when the pool is installed halfway in the ground. It does not cover structural damage due to improper installation procedures or frost heave.

The conditions of our standard warranty are in full force when the pool is installed halfway in the ground if the following conditions are met:

1. The pool must be full prior to backfilling.
2. Proper backfill material must be used, such as sand or sifted soil with no rocks or sharp objects.
3. Neither the wall, the frame, nor any of the coatings must be damaged during the backfilling process.
4. Backfill must be graded away from the pool 10°
5. The pool must be kept  $\frac{3}{4}$  full of water at all times. If the pool must be drained at any time to service or repair the liner, it must be done during the dry season when the groundwater level is below the level of the pool bottom, so that the pool does not collapse inward.

Any damage caused during the backfill operation or as a result of draining the pool will void the warranty. Wilbar International will not be responsible for any inward collapse of the pool wall or frame under any circumstances. Wilbar International will also not be responsible for any pool failure resulting from excessive water conditions such as flooding due to rainfall or other conditions.

Wilbar International  
50 Cabot Court  
Hauppauge NY 11788